

IITDh/IPS/2025-26/LPC/259
27th January 2026

Invitation for Quotation

Name of the Work: Construction of Kabaddi clay Court at IIT Dharwad Permanent Campus

Location: Permanent Campus IIT Dharwad

With reference to the aforementioned work, quotations are hereby invited for the said work. Interested vendors with experience in said works can submit their quotes (*as per Annexure-I*) on their official letterhead, duly attested, **in a sealed envelope via post / courier** to the following address:

To,
IPS Office (NE-113),
First Floor Admin Block,
Indian Institute of Technology Dharwad,
Permanent Campus, Chikmalligwad.
Dharwad-580011.

Deadline for submission: 10th February 2026 up to 1300 hours

NOTE:

- Any quotes received after 1300 hours on 10/02/2026 will not be accepted.
- Name of the Work / LPC number and Firm name should be mandatorily written on the sealed cover.

Sd/-
Executive Engineer
Indian Institute of Technology Dharwad

Annexure -1

BoQ for Construction of Kabaddi clay Court at IIT Dharwad Permanent Campus					
Sl No	Description of Item	UoM	Qty	Rate	Amount
1	Clearing grass and removal of the rubbish up to a distance of 50 m outside the periphery of the area cleared.	Sqm	397.00		
2	Earth work in excavation by mechanical means (Hydraulic excavator) / manual means over areas (exceeding 30cm in depth, 1.5m in width as well as 10 sqm on plan) including getting out and disposal of excavated earth, lead up to 50m and lift up to 1.5m, as directed by Engineer-in-Charge. All kinds of soil	Cum	179.00		
3	Supplying and stacking at site. Moorum.	Cum	151.00		
4	Supplying and stacking at site. Clay suitable for volley ball court made primarily from clay /soil /crushed brick.	Cum	60.00		
5	Filling available excavated earth (excluding rock) in trenches, plinth, sides of foundations etc. in layers not exceeding 20cm in depth, consolidating each deposited layer by ramming and watering, lead up to 50 m and lift up to 1.5 m.	Cum	230.00		
6	Earth work in surface excavation not exceeding 30 cm in depth but exceeding 1.5 m in width as well as 10 sqm on plan including getting out and disposal of excavated earth upto 50 m and lift up to 1.5 m, as directed by Engineer-in-Charge:	Sqm	25.00		
7	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level : 1:3:6 (1 Cement : 3 coarse sand(zone-III) derived from natural sources : 6 graded stone aggregate 20 mm nominal size derived from natural sources).	Cum	3.70		

8	Providing and laying at or near ground level factory made kerb stone of M-25 grade cement concrete in position to the required line, level and curvature, jointed with cement mortar 1:3 (1 cement: 3 coarse sand), including making joints with or without grooves (thickness of joints except at sharp curve shall not to more than 5mm), including making drainage opening wherever required complete etc. as per direction of Engineer-in-charge (length of finished kerb edging shall be measured for payment). (Precast C.C. kerb stone shall be approved by Engineer-in-charge).	Cum	6.00		
9	Providing Water based glossy paint (Green certified product) to Kerb Stones as per IS 164:2015 technical specifications, including cleaning & surface preparation	Sqm	175.00		
Subtotal ₹					
GST ₹					
Grand Total ₹					

(Contractors Sign and Seal)